



## Quench 555/565 Pre-Installation Checklist

Thank you for being a Quench customer! We are excited for your workplace to experience the great-tasting sparkling water from your new Quench 555/565. Before our certified technician can install your machine, the following pre-installation requirements must be completed.

### Water Supply

- 3/8" potable water supply terminating in 3/8" ball valve with 3/8" female pipe thread to connect to (ball valve must be accessible for service and installation)
- Minimum water pressure 14.5 PSI, 0.9 gallon per minute minimum flowrate
- Maximum water pressure 51 PSI
  - Must be a dedicated 3/8" water supply line with no other connections
  - Any water line or valve less than 3/8" is not acceptable
- Water shut-off valve must be located at low level with sufficient room for a 12" long fitting to be connected to the shut-off valve.

### Electrical

- Dedicated 115 VAC/60Hz/15 amp (standard 3-prong) electrical circuit
- Must be within 5' of machine location; **NO EXTENSION CORDS**

### Countertop Placement

- 1" diameter hole for the water line and CO<sub>2</sub> line to the Quench 555/565
  - Quench technicians are only permitted to drill up to 1-1/2" diameter holes through laminate or Corian counters. Any other surface or hole size must be pre-drilled prior to install.

### Ventilation

- If installed in an enclosed space, the machine requires 4" of space around the machine for adequate ventilation.

### CO<sub>2</sub> Supply

- CO<sub>2</sub> cylinder is on-site
  - If connecting to a bulk or existing CO<sub>2</sub> system, a CO<sub>2</sub> line terminating at 1/4" barbed shutoff valve must be available within 40" of the installation site
  - Minimum CO<sub>2</sub> pressure is 100 PSI

If you have any questions about the installation, call Customer Care at 888-554-2782

